

Schedule of Rate

Name of work: Outside painting & minor repairing work at Old T-IV Qtr NIT Silchar.

SI no	Item description	Unit	Qty.
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed. All kind of soil.	Cum	5.00
2	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar.	Cum	5.00
3	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix).	Cum	1.00
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level .		
	1:1½:3 (1 Cement: 1½ coarse sand: 3 graded stone aggregate 20 mm nominal size)	Cum	1.00
	1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	Cum	1.00
5	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size).	Cum	2.00
6	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum	0.50
7	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (1 cement :4 coarse sand)	Sqm	15.00
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level .		
	1:1½:3 (1 Cement: 1½ coarse sand: 3 graded stone aggregate 20 mm nominal size)	Cum	1.00
	1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	Cum	1.00
9	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. (i) Single socketed pipes		
	75 mm diameter	Rmt	20.00
	110 mm diameter	Rmt	30.00
10	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion.		
	(a) Coupler		
	75 mm diameter	Each	3.00
	110 mm diameter	Each	3.00
	(b) Single tee with door		
	75x75x75 mm	Each	3.00
	110x110x110 mm	Each	3.00
	(c) Single tee without door		
	75x75x75 mm	Each	3.00
	110x110x110 mm	Each	3.00

SI no	Item description	Unit	Qty.
	(d) Bend 87.5°		
	75 mm diameter	Each	3.00
	110 mm diameter	Each	3.00
11	Providing and fixing unplasticised -PVC pipe clips of approved design to unplasticised - PVC rain water pipes by means of 50x50x50 mm hard wood plugs, screwed with M.S. screws of required length, including cutting brick work and fixing in cement mortar 1:4 (1 cement : 4 coarse sand) and making good the wall etc. complete.		
	75mm	Each	5.00
	110mm	Each	10.00
12	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	Sqm	12600.00
13	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer	Sqm	12600.00
14	Finishing walls with Acrylic Smooth exterior paint of required shade: Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	Sqm	12600.00
15	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	Sqm	1200.00
16	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including valve, fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall		
	25 mm nominal outer dia Pipes	Rmt	20.00
	32 mm nominal outer dia Pipes	Rmt	20.00
	40 mm nominal outer dia Pipes	Rmt	120.00
	50 mm nominal outer dia Pipes	Rmt	120.00
17	Dismantling 15 to 40 mm dia G.I. pipe including stacking of dismantled pipes within 50 metres lead as per direction of Engineer- in-Charge. (a) Internal Work - Exposed on wall	Rmt	200.00
18	15 mm cement plaster on rough side of single or half brick wall finished with a floating coat of neat cement of mix : 1 : 4 (1 cement : 4 fine sand)	Sqm	25.00
19	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead : With cement mortar 1:4 (1cement: 4 coarse sand)	Sqm	100.00

Total Estimated Cost: Rs. 27,20,360.00 (DSR 2016 with 55.88% cost Index, & 1% labour cess)

Quoted Rate in percentage (%) over estimated cost (In word & fig)	
--	--

Signature of the Agency