

Schedule of Rate

Name of work: Outside painting work at Old T-V Qtr NIT Silchar.

SI no	Item description	Unit	Qty.
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :		
	1:1½:3 (1 Cement: 1½ coarse sand: 3 graded stone aggregate 20 mm nominal size)	Cum	1.00
	1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	Cum	1.00
2	Centering and shuttering including strutting, propping etc. and removal of form work for :		
	(a) Foundations, footings, bases for columns	Sqm	90.00
3	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. (i) Single socketed pipes		
	75 mm diameter	Rmt	20.00
	110 mm diameter	Rmt	30.00
4	Providing and fixing on wall face unplasticised - PVC moulded fittings/accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion.		
	(a) Coupler		
	75 mm diameter	Each	3.00
	110 mm diameter	Each	3.00
	(b) Single tee with door		
	75x75x75 mm	Each	3.00
	110x110x110 mm	Each	3.00
	(c) Single tee without door		
	75x75x75 mm	Each	3.00
	110x110x110 mm	Each	3.00
5	(d) Bend 87.5°		
	75 mm diameter	Each	3.00
	110 mm diameter	Each	3.00
5	Providing and fixing unplasticised -PVC pipe clips of approved design to unplasticised - PVC rain water pipes by means of 50x50x50 mm hard wood plugs, screwed with M.S. screws of required length, including cutting brick work and fixing in cement mortar 1:4 (1 cement : 4 coarse sand) and making good the wall etc. complete.		
	75mm	Each	5.00
	110mm	Each	10.00
6	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc complete	Sqm	13500.00
7	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer	Sqm	13500.00
8	Finishing walls with Acrylic Smooth exterior paint of required shade: Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	Sqm	13500.00
9	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	Sqm	1200.00
10	Painting with aluminium paint of approved brand and manufacture to give an even shade. Two or more coats.	Sqm	675.00
11	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead : With cement mortar 1:4 (1cement: 4 coarse sand)	Sqm	100.00

SI no	Item description	Unit	Qty.
-------	------------------	------	------

Total Estimated Cost: Rs. 27,10,230.00 (DSR 2016 with 55.88% cost Index, & 1% labour cess)

Quoted Rate in percentage (%) over estimated cost (In word & fig)	
------------------------------------------------------------------------------	--

Signature of the Agency