

Schedule of Rate

Name of work: Repairing of internal approach road at Old T-V Qtr NIT Silchar.

SI no	Item description	Unit	Qty.
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1½:3 (1 Cement: 1½ coarse sand: 3 graded stone aggregate 20 mm nominal size)	Cum	23.00
2	Centering and shuttering including strutting, propping etc. and removal of form work for : (a) Foundations, footings, bases for columns	Sqm	90.00
3	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	Sqm	1800.00

Total Estimated Cost: Rs. 17,62,830.00 (DSR 2016 with 55.88% cost Index, & 1% labour cess)

Quoted Rate in percentage (%) over estimated cost (In word & fig)	
--	--

Signature of the Agency